# FORMER TCSH POWER PLANT BUILDING GRAND TRAVERSE COMMONS



**Building Assessment Status** 

October 31, 2019

The Minervini Group LLC

## Impediments to Redevelopment





- Building size (26,000 sf) advantage & disadvantage
  - · 48 ft & 36 ft high ceilings on main level, 12 ft basement
  - Intermediate floors needed
  - SHPO Constraints re: changes to structure
- Multiple users likely needed for feasible re-use

## Impediments to Redevelopment (cont.)





- Adverse conditions = redevelopment challenges
- Daunting, unknown hazardous materials
- Massive, integrated equipment
- Supplemental assessments required and undertaken with GTCBRA support

## **Hazardous Materials Assessment:**

- Asbestos Containing Material in building:
  - Pipe insulation, window/door glazing, fire doors, wall plaster, roofing material, misc equipment, caulking, tank & boilers insulation, floor tiles/mastic



Pipe insulation =

>20,000 lin ft

Misc. insulation =

>31,000 sq ft

**Equipment containing ACM** 

= numerous

Hazardous Materials Assessment (cont'):



- PCB Containing Electric Equipment, etc.:
  - Transformers, electric panels, ballasts, drums
- Lead Based Paint:
  - Tanks, structural columns, staircases, platforms, basement walls, ceilings, etc.


## Supplemental Environmental Assessments:





- Concern about contaminated concrete floors, subsurface soils and groundwater under bldg.
- Sampling of concrete (15), subsurface soils (10), and groundwater under building (10).

Supplemental Environmental Assessments (cont.):



## Supplemental Environmental Assessment Findings:

- Subsurface soil, fill, coal, coal ash:
  - (1) PCE > GSIP/DC; No PCBs
  - (10) Metals > at least 1 criterion
- Groundwater:

No VOC; (1) Metals >GSI (Se)

- Concrete:
  - (7) PCBs present: (1) > criteria

No PNAs; (7) Metals: (2) > criteria




# Structural Assessments - Phase I (cont.)

 Typical structures and equipment whose removal during demolition will require structural reinforcements of building.



- Structural Assessments Phase I (cont.)
  - Typical structures and equipment whose removal during demolition will require structural reinforcements of building.



- Structural Assessments Phase I (cont.)
  - Typical structures and equipment whose removal during demolition will require structural reinforcements of building.

